Project Reference

Jones Engineering HQ Refurbishment Pembroke Road, Dublin





Details

Type of Job Basement Tanking, Remedial Works, Concrete Repair, Resin Injection

Products Maxseal Flex, Maxrite 500, Concreseal 5, Mesh, Maxplug, Maxseal

Super, Webac Injection Resin

Main Contractors Halton Construction

Location Dublin

Construction Completion 2019

Description

A major refurbishment of this landmark building was completed by Halton Construction. The fitout works transformed the building into luxurious office space for The Jones Engineering Group Head Office.

The fitout works included remedial works to the basement area. SURFASOLOGY complete partial waterproofing to the walls using the Drizoro Waterproofing System.

The works included stopping of running water and repairs to the substrate using hydraulic mortars and repair mortars from the Drizoro range. Some localised injecting of polyurethane resin was also completed. The properly prepared walls were then coated with the two-component, flexible, waterproof coating Maxseal Flex.

SURFASOLOGY™ - Waterproofing Specialists

Unit 143, Grange Drive **T** +353 1 832 1005

Baldoyle Industrial Estate E sales@surfasology.com



